

8	BILL No. 8:				
	SHANTY CLINIC				
	The UPS system consist of 2x 12kVA Riello UPS. The UPS are in bypass mode both UPS require a MAJOR service. The service will include the following:				
Item	Description	Unit	Qty	Rate	Amount
8.1	UPS MAJOR service				
8.1.1	Download event History	no.	2		
8.1.2	Upgrade firmware to latest revision	no.	2		
8.1.3	Cleaning of the UPSs	no.	2		
8.2	Replacement of batteries				
8.2.2	Test,Supply, deliver, install new VRLA 12V, 7Ah batteries complete with battery enclosure for both UPSs	no.	2		
8.3	Commissioning				
8.3.1	Commissioning the two systems complete in the presence of the Engineer	sum	1		
8.4	Miscellaneous				
9.4.1	Clean the floor (only the UPS room) to ensure the room is neat and in good condition.	sum	1		
8.4.2	Supply and install Caravan plug (5 pin plug)	no.	2		
8.4.2.1	EGA tube/skiting removal	sum	1		
8.4.2.2	Supply and install wire mesh basket and support the IT cables from the tray	m	10		
8.4.2.3	Neatly install the IT cables on the wire mesh basket	sum	1		
8.5	Test and confirm the UPS output DB circuitry and issue a CoC. This must include the following labels				
8.5.1	Sockets labelling	sum	1		
8.5.2	DB Labelling	sum	1		
8.5.3	Legend card	sum	1		
8.5.4	CoC (Only for UPS Output DB)	no.	1		
8.6	Supply a Service record book with two carbon copies	no.	1		
8.7	Service of the Air Condition Unit	Sum	1		
8.8	Provide Red top (shaved earth) plug top leads	No.	20		
8.9	Professional fees (15%, exclude P&Gs and Contingency)	%	0.15		
	Total for Bill No 8: Shanty Clinic Forward to Bill of Quantities Summary Page				