

9	BILL No. 9:				
	Sinqobile Clinic				
	The UPS system consist of 2x 12kVA Riello UPS. The UPS are in bypass mode both UPS require a MAJOR service. The service will include the following:				
Item	Description	Unit	Qty	Rate	Amount
9.1	UPS MAJOR service				
9.1.1	Download event History	no.	2		
9.1.2	Upgrade firmware to latest revision	no.	2		
9.1.3	Cleaning of the UPSs	no.	2		
9.2	Replacement of batteries				
9.2.1	Supply, deliver, install new VRLA 12V, 7Ah batteries complete with battery enclosure for both UPSs	no.	2		
9.3	Commissioning				
9.3.1	Commissioning the two systems complete in the presence of the Engineer	sum	1		
9.4	Miscellaneous				
9.4.1	Clean the floor (only the UPS room) to ensure the room is neat and in good condition.	sum	1		
9.4.2.1	Supply and install wire mesh basket and support the IT cables from the tray	m	10		
9.4.2.2	Neatly install the IT cables on the wire mesh basket	sum	1		
90.5	Test and confirm the UPS output DB circuitry and issue a CoC. This must include the following labels				
9.5.1	Sockets labelling	sum	1		
9.5.2	DB Labelling	sum	1		
9.5.3	Legend card	sum	1		
9.5.4	CoC (Only for UPS Output DB)	no.	1		
9.6	Supply a Service record book with two carbon copies	no.	1		
9.7	Service of the Air Condition Unit	Sum	1		
9.8	Provide Red top (shaved earth) plug top leads	No.	20		
9.9	Professional fees (15%, exclude P&Gs and Contingency)	%	0.15		
	Total for Bill No 9: Sinqobile Clinic Forward to Bill of Quantities Summary Page				