

Item No.	Description	Unit	Qty	Rate	Amount
	<u>SECTION No.2</u>				
	<u>BILL No. 1</u>				
	<u>EARTHWORKS (PROVISIONAL)</u>				
	<u>SITE CLEARANCE, ETC.</u>				
1.1	<u>Site clearance</u>				
1.1.1	Dig up and remove rubbish,debris,vegetation,hedges,shrubs and trees not exceeding 200mm girth, bush etc.	m ²	360		R -
1.1.2	Dig up and remove existing steel poles	No	49		R -
1.1.3	Remove existing damaged fence	m ²	153		R -
	<u>EXCAVATION, FILLING, ETC.</u>				
1.2	<u>Excavation in earth not exceeding 2m. deep</u>				
1.2.1	Trenches.	m ³	65		R -
1.2.2	Bases -wall	m ³	20		R -
1.3	<u>Extra over trench and hole excavations in earth for excavation in</u>				
1.3.1	Soft rock.	m ³	15		R -
1.3.2	Hard rock.	m ³	8		R -
1.4	<u>Extra over all excavations for carting away</u>				
1.4.1	Surplus material from excavations and/or stockpile on site to a dumping site to be located by the contractor (up to a radius of 5km - return distance not covered)	m ³	55		R -
1.5	<u>Risk of collapse of excavations</u>				
1.5.1	Sides of trench and hole excavations not exceeding 1,5m deep including keeping excavations free from water	m ²	380		R -
1.6	<u>Keeping excavations free of water</u>				
1.6.1	Keeping excavations free of water other than subterranean water	Item	1		R -
1.7	<u>Earth filling obtained from excavations and/or prescribed stock piles on site compacted to 95% Mod.</u>				
	<u>AASHTO density</u>				
1.7.1	Backfill to trenches, holes, etc.	m ³	30		R -
<u>EARTHWORKS CARRIED TO SECTION SUMMARY</u>		R			-